

Tract 7-24 (Scooby) – Flambeau River State Forest

Parts of: W1/2NE, NWSE, NENW, SENW, NESW Sec. 14, T38N-R3W, Town of Winter, Sawyer County.

70 Acres

<u>Species</u>	<u>Estimated Volume</u>	
¹ Mixed Pulp	2700 tons	Minimum Acceptable
Basswood	240 tons	<u>Bid for Entire Sale</u>
Aspen	1000 tons	\$31,440.00
Ash	52 MBF	
² Mixed Saw	13 MBF	

Utilization specifications for cordwood will be 1 stick (100 inches) to a 6-inch top diameter.

¹Mixed pulp includes 63% ash, 25% hard maple, 10% red maple, 2% cherry, ironwood and birch.combined.

²Mixed saw includes 7 MBF hard maple, 5 MBF basswood, 1 MBF red maple, and a small amount of yellow birch.

Other species not mentioned will be charged at the mixed pulp/saw price.

The performance bond will be 15% of the total sale value. Contract ending date will be **June 30, 2028.**

SPECIAL SALE CONDITIONS:

Equipment use will only be allowed during very dry or frozen ground conditions due to wet soil conditions. Access may be restricted to frozen conditions due to soil conditions of trail.

To make access operable during very dry conditions, existing trail will most likely need pit run material. The state will provide the pit run material, but it will be the responsibility of the contractor for loading/hauling/leveling any pit run.

Harvesting in selection area allowed outside of April, May, and June.

Use of a continuous rotating saw head will not be allowed in the selection area or the canopy openings.

If decking on Tower Hill Road, all slash, ends, and logging debris including bark will be removed from the roads and ditches concurrently with each truckload.

Tower Hill Road is also a snowmobile/ATV trail. 3” of packed snow will be maintained on Tower Hill Road, weather permitting.

Proposed roads/skid trails are indicated on map and may be used to access the harvest areas. Modifications may be made with approval of forester. Other new construction must be approved by forester.

Culvert placement is needed at drainage. DNR staff will complete the placement of the culvert. This will need to occur prior to harvesting.

Contractor is required to close road at designated map location by placing a debris berm.

No slash to be left beyond the red paint line into the State Natural Area. No slash to be left beyond the red line along Lake of Pines. All slash within 200’ of Lake of the Pines will be lopped and scattered to within 2’ of the ground.

All additional restrictions listed in prospectus and standard contract apply unless specified.

Contact Heidi Brunkow with questions at 715-332-5271 ext. 106 or heidi.brunkow@wisconsin.gov